
Construction Details





ARITH COMPANY LIL 地址: 台北市復興北路427巷30 電話: (02)2717-5038 傳真: (02)2717-5039 e-mail: taipei@arith.com.tw 網址: http://www.arith.com.tw





- Watertight
- G-235 (Z700 Metric) Hot-dip galvanized steel panels
- Insulated with 2" expanded polystyrene insulation

2 Coil Support Beams

 Prevent contact between coil and primary liner

Glycol Connections

· Grooved for mechanical coupling

4 Galvanized Steel Coil

- · Continuous serpentine, steel tubing
- Hot-dip galvanized after fabrication (HDGAF)
- Pneumatically tested at 190 psig
- Rated for 150 psig operating pressure

Primary Liner

- Single piece
- 48-hour integrity test before shipment

6 Extruded Polystyrene Insulation

 1.5" thick, installed between primary and secondary liners

Secondary Liner/Vapor Barrier

 Prevents moisture from penetrating through the insulation

8 Wall Panel

- Heavy-gauge galvanized steel with double brake flanges
- 3" of expanded polystyrene insulation

Sight Tube

 Visual indicator of water level corresponding to the amount of ice in unit

Operating Control (Not Shown)

- High-level float switch and low water cutout mounted on the outside of the tank
- Can be provided for one tank (standard) or all tanks (optional)

Ice Inventory Sensor (Optional)

 Differential pressure transmitter provides an electrical 4-20 mA output signal which is proportional to the amount of ice in inventory



